


The LHC Final Alignment



T. Dobers, M. Jones, D. Missiaen, C. Podevin, J.P. Quesnel

- Introduction to the LHC Project
- the initial alignment
- The final alignment
- The measurements
- The PLANE software
- Conclusions



□ LHC

- ✓ 27 km proton-proton collider
- ✓ ~2000 cold components
- ✓ Two beams in two different cold bore tubes
- ✓ 4 interaction points
- ✓ Divided in 8 sectors which are cooled down one by one
- ✓ **First beam in may 2008**





❑ From the geodetic network

- ✓ measured from the position of the LEP collider main quadrupoles
- ✓ Using levelling, horizontal angles, Mekometer distances, gyroscopic orientations and offset measurements


❑ How

- ✓ Using optical level NA2, TDA5005 distances, offset measurements
- ✓ Local horizontal smoothing


❑ Accuracy

- ✓ In order to obtain the best absolute position
- ✓ A relative position of
 - ❑ 0.15 mm at 1 σ in z
 - ❑ 0.25 mm at 1 σ in x and y

The First Alignment



The First Alignment





- ❑ **Operation that**
 - ✓ Suppress the steps which perturbates the particle beams
 - ✓ Improve the relative accuracy of the components
 - ✓ Has to take place when the magnets are « cold », i.e. all the constraints have occurred
- ❑ **What magnets**
 - ✓ All cryo-magnets not only the MQs
 - ✓ To prevent the shearing off the tubes in the interconnect
- ❑ **Accuracy**
 - ✓ Deviation to a smooth line not exceeding of 0.15mm at 1 s
- ❑ **Steps**
 - ✓ Roll angle, Vertical and Horizontal measurements
 - ✓ Calculation of the smooth line with « PLANE »
 - ✓ Displacement of the magnets out of tolerance

- ❑ With a special instrumentation installed on two fiducials
- ❑ No important measurements
- ❑ Slight degradation of the beam
- ❑ Per sector, 3 days of measurements by a team of 2 persons
- ❑ Corrections



- ❑ Instruments
 - ✓ Digital levels DNA03
 - ✓ Illuminated staff
- ❑ Measurement sequences




❑ Advantage

- ✓ Regular sequence

❑ Drawback

- ✓ Inequality of distances




□ Scale factor


- ✓ a staff problem which was too tight by 0.2mm on 800mm
- ✓ Measurements corrected by 1.00025

□ Collimation problem


- ✓ Check-and-adjust was giving surprising values day from the other
- ✓ The difference of heights of the turning points was not the same from station N and station N+1
 - ✓ the difference of distances between Stations is ~11m

□ When a significant collimation error is found, measurements were corrected






- ❑ Discrepancies between both runs
- ❑ No influence on the relative position of magnets
- ❑ Still to be investigated




- Levelling blocked at each side of the sector on deep references
- No big deviations
- Points to be moved calculated by plane (later in this talk)
- Saw tooth phenomena visible for most of the sectors




- ❑ Length of the wave is a half cell length ~53 m
- ❑ Probably due to a collimation error of the NA2 used during the initial alignment (unstability of the optical axis)
- ❑ Large Influence when no equality of distances

Levelling of the LHC




- Levelling has been blocked on all the deep references
- No large deviations



- ❑ Offset = Distance to a Stretch wire
- ❑ Redundancy of 3 for MQs and 2 for MBs
- ❑ Protection inside a tube
- ❑ 2 weeks per sector for a team of 3 persons



LHC 7-8 lissage à froid - écartométrie- distribution des résidus après compensation




- ❑ Sectors 78 and 45 measured at cold
- ❑ Very good quality of the measurements

Sector	Number of measurements	r.m.s (mm)	Average (mm)
45	920	0.051	0.009
78	877	0.040	-0.007


- For each sector, compensation avec 1 fixed pt, and orientation pt and radial constraints
- No big relative deviations
- Points to be moved calculated by « Plane »

Sector 78 horizontal deviations




□ What is Plane ?


- ✓ Software to calculate a smooth line and the points to be displaced
- ✓ Principles : windows and polynomials
- ✓ Parameters : size of the window and Tol above which the points are rejected
- ✓ Works in vertical and horizontal plane



Windowing with Plane



Smoothing of two Sectors



□ Vertical

Sector	Stdev before smoothing (mm)	Stdev after smoothing (mm)	Points to be moved
1-2	0.16	0.10	41
2-3	0.17	0.12	63
3-4	0.18	0.11	84
4-5	0.15	0.11	45
5-6	0.15	0.10	49
6-7	0.13	0.10	20
7-8	0.19	0.11	53
8-1	0.16	0.11	67

□ Horizontal

Sector	Stdev before smoothing (mm)	Stdev after smoothing (mm)	Points to be moved
4-5	0.19	0.11	65
7-8	0.17	0.11	41

- 53 magnets moved/23%
- Good improvement of the smoothing process
- in both directions, the specification of 0.15 mm is reached
- Same accuracy in vertical and horizontal

- ❑ **The final alignment smoothing is very important**
 - ✓ For detection of big errors or movements
 - ✓ to improve the quality of the relative position of magnets just before a physics run
- ❑ **Instrumentation and methodology**
 - ✓ Very good quality of the offset measurements
 - ✓ Still difficult to have good levelling measurements
- ❑ **The results for LHC**
 - ✓ All sectors smoothed for the roll angles and in vertical plane, only two sectors in the horizontal under cold conditions
 - ✓ In both planes no important relative deviations
 - ✓ ~53 Magnets moved/sector
 - ✓ deviations under 0.15 mm rms as specified