


## ILC and Related Programs Chris Adolphsen

©Rey.Hori

# ILC Overview

## RDR ILC Layout




- Design fairly mature – aiming for a TDR at end of 2012 with updated costs
- In 2009, proposed changes to the 2006 RDR design to reduce costs 10-15%, including
  - Single Linac Tunnel in combination with a more reliable RF distribution scheme
  - Halve the number of bunches per pulse
  - Halve the damping ring size
  - Consolidate the central region tunnels
- Advisory group rejected wholesale adoption of these changes - currently reviewing each one with expanded oversight by HEP community

# SLAC ILC Program

- FY10 budget ~ 12 M\$ with about half for HLRF. Includes:
- High Level RF (HLRF) development
  - Marx Modulator
  - Sheet Beam Klystron
  - Klystron Cluster Scheme (KCS) for rf distribution
  - Local rf distribution (also supports FNAL NML program)
  - Cavity power couplers (also supports FNAL NML program)
- Electron Source - generate ILC-like bunch train
- Damping Rings
  - Electron cloud simulations and mitigation for positron ring
  - Fast kickers for the Damping Rings
- Beam Delivery System (BDS)
  - Machine-Detector Interface issues such as vibration and magnet-beam stay-clear
  - Final Focus optics tests at KEK ATF2
- Other
  - Beam physics, wakefield and operational issues in the Main Linacs
  - Global controls: adoption of the high availability ATCA crate standard

# SLAC RF System Development





## Goals:

Develop more reliable and lower cost L-band RF source components

Verify performance goals of the rf system

# SLAC P1 Marx Modulator

(120 kV, 140 A, 1.6 ms, 5Hz)






- 11 kV per cell (11 turn on initially, 5 delayed for coarse droop compensation)
- Switching devices per cell: two 3x5 IGBT arrays
- Vernier Cell ('Mini-Marx') flattens pulse to 1 kV





# Marx Modulator and 10 MW MBK at ESB

More than 2000 Hours of Operation







Modulator Voltage with Different Levels of Droop Compensation



Toshiba 10 MW Multi-Beam Klystron (MBK)


# Evolution to the P2-Marx

- 2nd Generation design builds on P1 experience
- Improved high availability architecture
  - Truly modular topology; single repeated cell design
  - Droop compensation (via PWM) integrated into each cell
  - 4 kV cell voltage eliminates series switch arrays
- Prototype cell undergoing testing
- Expected completion in FY11





# Sheet Beam Klystron Development

An elliptical beam is focused in a periodic permanent magnet stack that is interspersed with rf cavities – gives same high efficiency (65%) as multiple beams but less expensive with use of permanent magnet focusing







# Beam Tester Results



A/cm<sup>2</sup>






During the tests, ran very low pulse rate as 'sputtered' carbon from the beam probe shield poisoned the cathode.

A vertical asymmetry was observed in the measured current density profile that was partially corrected using a 900V and 0V bias on the upper and lower focus electrodes, respectively. The resulting current density is shown above - an ideal elliptical beam profile outline is superimposed in white.


# Two-Cavity Stability Test

Found no simple means to suppress the modes in simulation without doubling the drift tube height to decrease cavity coupling and a using solenoidal magnet to increase the focusing strength.

Built a two-cavity oscillation device that will be used to verify the predicted regions of stability vs magnetic field. Stop further work as developing a solenoid-focused SBK would extend beyond the ILC TDR timescale.




# Klystron Cluster Concept



Each tap-off from the main waveguide feeds 10 MW through a high power window and probably a circulator or switch to a local PDS for a 3 cryomodule, 26 cavity RF unit (RDR baseline).

- RF power “piped” into accelerator tunnel every 2.5 km
- Service tunnel eliminated
- Electrical and cooling systems simplified
- Concerns: power handling, LLRF control coarseness


# Klystron Cluster Surface Building Concepts by Holabird/Root






# Single Tunnel Layout with KCS

RF Waveguide




Americas Region




European Region


# Coaxial Tap Off (CTO)



WC1375




# KCS Test Bed at SLAC ESB



# Phase I Demonstration

(Just Starting)




Adjusted input coupling ( $\beta = 3$ ) and will resonantly charge the line ( $\tau = 8 \mu\text{s}$ ) to field levels equal to those for 350 MW transmission (requires only 0.5 MW of klystron power). Do this under pressure (2 bar absolute) and under vacuum ( $< 1\text{e-}6$  Torr).



# Phase II Demonstration


(To Be Completed in 2012)

Develop bends and configure a 160 m resonant ring to test them and a final design tap-in/off. Stored energy is about 1/5 of the worst case in the ILC with speed-of-light limited klystron shutoff time.





# Local RF Distribution Modules




Four, two-cavity distribution modules were individually high power tested and then shipped to FNAL in FY09



Elliptical Variable Tap-Off (VTO)



# Building Simpler VTO For Next CM



Use commercial 'folded' Magic Tee's

Put remotely controllable phase shifters into U-bends – relative phase controls power split


Match ideally unaffected by position

No bellows but need 'finger' stock to cut off RF

# TTF-3 Coupler Design

Design complicated by need for tunability ( $Q_{ext}$ ), dual vacuum windows and bellows for thermal expansion.

Coaxial Power Coupler







# Coupler Assembly in the SLAC Class 10 Cleanroom



# RF Processing of Coupler Pairs


Processing of first pair sent to FNAL:  
Power (MW) -vs- Time for Pulse Widths of  
50, 100, 200, 400, 800, 1100  $\mu\text{s}$

Processed Fast by Historical Standards




# Fabrication Simplification

Currently building a 'cold' coupler section using TIG welding and induction brazing of parts assembled using conventional brazing techniques (Cu plate parts first, then braze and TiN coat window before final assembly). The antenna is hollow and vents to the warm section.




Conventional brazements and final assembly




# Electron Source R&D

Bunches are generated when the GaAs photocathode is illuminated by pulses of light from a drive laser – for ILC, use circularly polarized light to generate polarized electrons






## SLAC Polarized 120 kV Electron Gun




## Jefferson Lab Polarized 100 kV Electron Gun




↑  
Currently assembling a multi-pass Ti:sapphire amplifier laser system at SLAC to produce 790 nm, 5  $\mu$ J pulses at 3 MHz that will generate the an ILC-like bunch train: 2600,  $3e10$ , 1 ns long electron bunches per pulse with  $> 80\%$  polarization

# JLab “Inverted” Gun

In parallel, JLab will try to increase gun HV to 200 kV (2.8 MV/m cathode, 7 MV/m max) using an ‘inverted’ insulator design to reduce space-charge induced emittance growth




# Polarized Electron Source Timeline



# SLAC Participation in CEsrTA e-Cloud Studies

- Redeployed 3 PEP-II experimental hardware projects in CEsrTA, earlier in 2009:
  - SEY *in-situ* measurement system
  - Groove Chambers
  - PEP-II Chicane and Grooved Chamber
- Development of electron cloud models based on CEsrTA experimental data and support of simulation effort.
- Participation to CEsrTA machine studies

M. Palmer and D. Rubin, Cornell Univ.”...We are extremely grateful for the participation of the entire SLAC team. We look forward to continued collaboration with SLAC physicists as we transition from an installation and commissioning phase to low emittance operation of the ring and beam dynamics studies in this regime.”






# ILC Damping Ring

SLAC is strongly involved in the ILC Damping Ring (DR) system with the:

- Coordination of an international Working Group to address:
  - Recommendation of technical mitigations against the electron cloud formation
  - Reduction of DR size from 6km to 3km
  - Feasibility of shorter bunch spacing from 6ns to 3ns
  - Feasibility of 10Hz DR operation to double luminosity
  
- Support the electron cloud simulation effort:
  - Development of state-of-the-art simulation codes of e-cloud generation and the resulting beam instabilities
  - Characterization of the electron cloud formation in the rings
  - Characterization of instability thresholds

E-cloud Trapping in a Quadrupole




Mitigation in the ILC Damping Rings

| DR element        | % ring | Antechamber need        | Coating      | Mitigation          | Additional Mitigation |
|-------------------|--------|-------------------------|--------------|---------------------|-----------------------|
| DRIFT in STRAIGHT | 54     | No                      | NEG & Carbon | Solenoid            | Grooves               |
| DRIFT in ARC      | 33     | Downstream of BEND only | NEG          | Solenoid            | Grooves               |
| BEND              | 7      | Yes                     | TiN          | Grooves             |                       |
| WIGG              | 3      | Yes                     | TiN          | Clearing Electrodes |                       |
| QUAD & SEXT       | 3      | Downstream BEND / WIGG  | TiN          | Grooves             |                       |




# SLAC DR Kicker Modulator R&D

- SLAC program continues to investigate two approaches to meet the challenging waveform requirements of ILC damping ring kickers:  $\pm 5$  kV into  $50 \Omega$ , 2 ns duration,  $\sim 1$  ns rise/fall time
- Adder Program
  - Hybrid MOSFET/driver
    - $\sim 1$  ns switching time (demonstrated FY08)
    - Improve assembly technique
    - Evaluate thermal stability
  - High bandwidth adder topologies
    - Preservation of pulse fidelity (FY09)
    - Extend to ILC parameters
- Opening Switch Program
  - Uses Drift Step Recovery Diodes (DSRDs)
  - 2-ns prototype demonstrated (FY08)
  - Developing 4-ns modulator for ATF2




# ILC Final Focus Optics and Instrumentation Test Facility at ATF2, KEK



- **Experimental verification of the ILC FFS scheme**
  - Development of beam tuning and modeling codes
  - Goal A: focus vertical spot at IP to 37nm (single bunch)
  - Goal B: maintain IP vertical position with few-nm precision (multi-bunch)
- **Development of ILC instrumentation**
  - High resolution BPMs, magnet movers, Fast feedback, Laserwire, beam size monitor, high-availability power supplies, fast pulser, super conducting final doublet...
- **Education of young generation for future linear colliders**
  - Active participation of graduate students and post-docs.

# Scaled Test of ILC Final Focus Optics



- Scaled design of ILC local-chromaticity correction style optics.
- Same chromaticity as ILC optics.
- At lower beam energy, this corresponds to goal  $\sim 37\text{nm}$  IP vertical beam waist (300 nm achieved to date).

## Typical DR Parameters

$\varepsilon_x / \varepsilon_y = 1.3\text{nm} / 8\text{-}10\text{pm}$   
 $E = 1.282\text{ GeV}$

## ATF2 IP parameters

$\beta_x / \beta_y = 4\text{cm} / 0.1\text{mm}$   
 $\sigma_x / \sigma_y = 6\mu\text{m} / 37\text{nm}$   
 Rep. Rate = 1.56 Hz

# SLAC Contributions to ATF2

- Hardware
  - Final doublet quads, FFS sextupoles
  - High-availability Power Supply system for FFS magnets
    - Currently upgrading matching quad system to give bi-polar functionality
  - Magnet mover system for FFS magnets
    - System used at FFTB, new controls s/w for ATF2
  - EXT & FFS C-band cavity BPM electronics
  - IPBPM cavity BPM electronics
    - Currently investigating modifying existing SLAC C-band electronics with improved digitizer system.
  - Multiple OTR system (5 OTRs) for fast emittance and coupling measurements and correction in EXT
  - New EXT stripline BPM readout system, using analogue readout system taken from LCLS design with modified digital readout.
  - Carbon wire scanner system for downstream IP location
    - Now also modifying IP installation to include additional Carbon wire system
- Controls software
  - Built and maintain EPICS controls for SLAC supplied hardware
  - Built and maintain EPICS control environment (save/restore, archive, backup etc)
  - Built and maintain offline simulation layer for EPICS controls
- High level application software
  - Built and maintain portable high-level controls interface system (“ATF2 Flight Simulator”)
  - Built and maintain many high-level machine apps (e.g. IP tuning, orbit feedbacks, dispersion and coupling correction...)
- Simulation
  - Design and testing of FFS tuning knobs
  - Analysis of tuning performance, comparison with ILC etc..



# FNAL Project X


- Build on our experience with ILC rf sources to provide wall-plug to coupler rf systems for the 1.3 GHz portions of the CW and pulsed SC proton linacs being considered
- Have scoped 25 kW CW sources: solid state (10 kW unit shown in photo), IOTs and klystrons
- Expect to get ~ 500 k\$ in FY11 to do solid state source development
- Also, the SLAC ACD group is currently working with FNAL to evaluate/design a 53 MHz cavity for the Main Injector Upgrade
- Other efforts may include design of the beam chopper and linac beam dynamics studies




# Muon Accelerator R&D

- Exploit extensive experience with breakdown in normal-conducting X-band (11.4 GHz) structures, and recent experience with L-band (1.3 GHz) systems to help in the design of the 201-805 MHz cavities required for muon acceleration. Program could include:
- Simulation of dark current trajectories in strong magnetic fields and the cavity surface heating they induce
- Design a magnetically insulated cavity at S-band (2.856 GHz)
- Build a new 805 MHz pill-box cavity using the techniques that have proved successful at SLAC (the FNAL one is nine years old and fairly 'beat-up').

Magnetically Insulated Cavity



FNAL 805 MHz Pill-Box Cavity



# Summary

- Contributing to key ILC design and development issues:
  - R&D aimed at cost saving including development of Marx modulator and a surface-based rf source scheme for a single tunnel Main Linac
  - Linac operation with a spread of cavity gradients
  - Polarized electron source demonstration
  - E-cloud mitigation in the Damping Rings
  - Beam delivery studies, ATF2 small spot demonstration and machine detector interface issues
- L-band and X-band experience a good match to future initiatives
  - CW or pulsed SC proton linac
  - Low frequency, high gradient, magnetically-immersed cavities for muon acceleration