

11

Decommissioning

The NLCTA, by reason of its low power and limited expected hours of operation, will generate only a small quantity of radioactive material. This will be comprised of parts of the accelerator structure, the beam dump, and possibly some parts of the concrete shielding adjacent to the dump.

The NLCTA is not expected to generate any hazardous wastes in the course of its operation.

SLAC has a procedures manual for the management of radioactive material, and a policy for the assignment of responsibility for the management of decommissioning of both conventional and technical facilities. The facility will not present any special problems in the execution of these policies and procedures.