




Stanford
Linear
Accelerator
Center

BROOKHAVEN
NATIONAL LABORATORY




~宇宙と物質の
起源と構造を探る~
KEK
高エネルギー加速器研究機構

The X-band Linear Collider preparation - *status and plans*

presented by Marc Ross on behalf of the NLC / GLC groups

13.11.2003



RF System: Copper Accelerator

- *Design:* KEK, Fermilab and SLAC
- *Production:* KEK, Fermilab, LLNL and SLAC
- *High Power Test:* KEK and SLAC

X-band test facilities

GLCTF at KEK

2003

1 test position /w full power @100Hz
(3 in 2004)

beam in 2005

2 x 50 MW pk klystrons



KEK Tristan Assembly Hall

NLCTA at SLAC

1996

4 test positions /w full power @60 Hz
(8 in 2004)

170 ns beam

9 x 50 MW pk klystrons



SLAC End Station B


NLC / GLC: the X-band Linear Collider



GLCTF at KEK in April 2003

????????????

Drawing S-Anaki: See Shield Modify by 20 APR 2000



The Accelerator Test Facility at KEK

1.3 GeV Damping Ring and S-band linac
100 MW X-band structure testing
1998 →

The world's largest LC test facility

World's lowest emittance beam:

$$\epsilon_y = 4 \text{ pm-rad}$$

below X-band LC req's

Tevatron 1984: “ Make and test magnets
(*structures*) as fast as possible”

A. V. Tollestrup



**X-band
structure
production**

- Structure RD: *three – fold focus*
 - *Electrical design*
 - coupler, power flow and gradient
 - *Materials / fabrication process*
 - particulates, surface, grain size and chemistry
 - *Test and understand; validate with beam*
 - diagnostics, post-mortem and analysis

- 2003 structure production rate:
 - 16/year
 - (almost) fully featured


RD Goal:
Fully featured structure (slots...)
Maximum efficiency
Sustainable gradient
‘breakdown rate’

Structure fabrication includes:




- good copper
- high quality commercial machining
- light chemical etch
- in-house brazing, diffusion bonding
- vacuum fire or hydrogen fire
 - increases grain size
- in-situ bake
- nominal clean room process

SS inclusion in cell wall – covered with and surrounded by breakdown ‘craters’ →




Test structure performance

Operations history – Test Structure (2002)



Linac/ Structure parameters




65MV/m unloaded gradient
7.5 km / linac @ 500 GeV

Adapt power, surface field
and gradient along length
to improve breakdown
performance

Maintain the dipole mode
performance needed for
beam quality → 'detuning'


Deflecting mode detuning ca. 1968 → the commissioning of SLAC



- breakdown events are grouped in time: 1/hour is really a single group of 10 in a few minutes
 - seen at SLC with the high gradient positron source accelerator


Structure performance summary

Breakdown Rates at 400 ns Pulse Width



Breakdown rates depend on process history

Structure Testing & Processing




from machined
cells to high
gradient in 10
weeks – *FNAL*,
SLAC & *KEK*

NLCTA/GLCTF operate ~ 4000 hours / year

Production rate:
~ 16 x 0.6m/year
= 10 m / year
= 650 MeV/year

X-band RF Distribution



Dual – mode SLED II
Compression System
*Hybrid, delay lines and
couplers
all ‘overmoded’ for loss
reduction*

Full scale, nominal system –
phase 1: *not connected to
structure*


Milestone:
475 MW, 400ns
at the load tree

NLC / GLC: the X-band Linear Collider


Marc Ross – *SLAC*

SLED hybrids: 1973-2003


1973




Sled Head Simulations



SLED 4 port hybrid




SLED 2 'warm' tests




— $10^3 \times$ Measured Power at the TE11 Arm
— Measured Power at the TE01 Arm

Comparison between the signal seen at the TE11 Arm with the signal at the TE01 Arm



- Gain tests of the dual mode system showing inter-modal contamination and total gain $\sim 3.2 \rightarrow$ close to theoretical max





**Connect
SLED 2 to
NLCTA
March 2004**


- Connect the output of the new SLED 2 system to the structure testing stations in NLCTA
 - Doubles the number of testing stations
- complete NLC/GLC RF system

**75MW
Klystron
X band
power source**

- Toshiba/KEK & SLAC
- Permanent magnet focusing
 - efficiency improved 2x without solenoid
- tested successfully summer '03




**75MW, 120Hz, 1.6 μ s operation (511kV, 6% collector
notch, 53% eff, 56dB gain, not saturated)**




Induction – solid state power converter


Goal: 500 KV
120Hz
1.6 us




Today: 8/4-Pack in NLCTA



II. Hybrid 2-Pack on 8-Pack NLCTA (3/04)




**I. Hybrid 2-Pack on 4-Dog Bldg 15
(12/03)**





**III. 2-Pack Integrated Xfmr Dsgn
(9/04)**

Metglas Cell w/ Boards



NLC Oil Cooled Metglas Core Assembly



X-band RF summary

- **Power converter:** *tested at full voltage,*
 - reduced repetition rate
- **Source:** *2 successful tubes with ~ 100 hours*
- **Distribution:** *assembly completed; warm test successful*
 - → high power testing began this week
- **Structure:** *~ fully slotted structures*
 - → breakdown rates at full unloaded gradient ~ 2 x above goal

- The Accelerator Subcommittee of the US Linear Collider Steering Group (USLCSG) has been charged by the USLCSG Executive Committee with the preparation of options for the *siting* of an international linear collider in the US.
 - This group will (probably) produce a ‘bid’ to host the linear collider in the US
 - ‘options’ → → either warm or cold
 - not TESLA nor NLC/JLC but → ‘equivalent performance machines’
- The ‘Accelerator Subcommittee has produced a written evaluation of cold/warm 0.5 (upgrade to 1) TeV cm with:
 - cost
 - risk
 -
 - availability
 - site studies

publication 12.2003?

Cost comparison

- Using DoE standard costing and overhead rules
- Using component costs developed for previous NLC & TDR exercises

Comments:

- US DoE rules (add-ons – mostly direct & not proportional) tend to wash out warm/cold differences in total project cost
- Base cost difference reflects larger cold machine ring and linac

Risk defined: *the chance that one fails to meet basic Luminosity or Energy goals*

Identify those failure modes that are most germane to the technology choice.

- risks common to both choices downplayed

Distinction between *availability/reliability* and *risk*:

- *Availability*: design parameter, amenable to direct engineering approach
 - Things *will* break
- *Risk*: chance one fails to meet basic goal:
 - fundamental failure of theory/RD/design process
 - basic goal: 500 fb⁻¹ at 500 GeV within 5 years
 - A familiar example of a risk:
 - 1) failure to meet availability goal...



Risk analysis

- follows textbook '*scoring & ranking*' process with points related to:
 1. comprehension of problem
 2. stretch from present technology & level of engineering required
 3. impact on machine performance
 4. project stage at which failure is detected
 5. likely mitigation process
- discovered:
 - large fraction of risks are common to both warm / cold
 - *control system and machine protection issues are very serious*
 - beam delivery issues also serious
 - (detection is late in project)

**HEP must aggressively attack
Controls/Instrumentation issues**

- System challenges are clearly greater for HEP machines
- Look at the shift SLAC.DESY.KEK accelerator groups away from HEP toward nuclear/synchrotron radiation/FEL physics and technology
 - very active growth field
- Many accelerator designers have *no intrinsic connection* with HEP

U.S. Linear Collider Site Studies




California



Illinois

Sample sites studied in Illinois and California
Development of site criteria...




USLCSG Site study '90'

Central Valley
near Livermore
Nat'l Lab



→ very near 19th
century coal
mining town of
TESLA, CA
(1850-1920)



(2001)



(1898)






- *primarily based at KEK ATF*
- Laser-based beam size monitors → ‘*laserwire*’
 - UK/KEK/SLAC/DESY
- precision RF beam position monitors → ‘*nanoBPM*’
 - SLAC/KEK
- fast intra-train feedback → ‘*FONT*’
 - UK/SLAC/KEK
- bunch length diagnostics → ‘*LOLA*’ at TTF2/VUV FEL
 - DESY/SLAC

Higher mode resonances

misaligned laser injection


higher order mode resonate in the cavity

Laser-wire at ATF




mirror distortion
?

transmitted light
profiles of each mode




mode degeneration TEM01/10

mirror distortion to split these modes



Beam-based Feedback (FONT)

- **Intra-train beam feedback
is last line of defence
against ground motion**
- **Key components:**
- **Beam position monitor
(BPM)**
- **Signal processor**
- **Fast driver amplifier**
- **E.M. kicker**
- **Fast FB circuit**



**Nano-meter
BPM studies
at ATF**

- achieved position resolution (June 2003)
 - trajectory angle resolution (June 2003)
 - achieved in FFTB (1997)


 - expect $S/N=2$ for 1 nm offset (2004)!

 - Goal resolution: (March 2004)
 - Goal angle resolution – single BPM
 - (angle resolution from three BPM line)

 - Goal position prediction error (2m baseline)
 - Goal position prediction error (5m baseline)
- | | |
|-------------------|----------|
| $y \rightarrow$ | 40 nm |
| $y' \rightarrow$ | 10 urad |
| \rightarrow | 25 nm |
| $y \rightarrow$ | 2 nm |
| $y' \rightarrow$ | 500 nrad |
| $y' \rightarrow$ | 2 nrad |
| $y_2 \rightarrow$ | 5 nm |
| $y_2 \rightarrow$ | 13 nm |


Closeup of BINP cavity BPM's with SLAC/KEK $x x' y y'$ movers – 03/03

Resolution tests rely on data from 'triplets' of BPM's – *beam trajectory assumed straight*



Bunch Length - Transverse deflection

Old idea – 1965 ‘LOLA IV’
Testing in linac sector 29



Brute force
Calibrated
Expensive
Excellent resolution

SLAC LCLS – Krejcik/Emma (EPAC 02)
SLAC/DESY TTF2

NLC / GLC: the X-band Linear Collider

Comment:

- Stong, proven, international collaboration (esp. high energy physicists) is an extremely valuable (*political and practical*) asset
 - *urgent*: work to strengthen accelerator development collaboration across the spectrum of RD effort in parallel with the development of design team

Conclusions

Next 6 months are pivotal for the X band technology demonstration

- present status encouraging
- collaboration KEK-SLAC-Fermilab has good vitality

**US DoE
Statement**

- US DoE Office of Science presented its 20 year plan
Monday 10.11.2003
- *The linear collider is the top ranked ‘mid-term’ project*
 - Secretary Abraham’s comments are very encouraging
- It is more important than ever that we make the
technology choice and get working on one
machine